

SUDA

STATE URBAN DEVELOPMENT AGENCY

HEALTH WING

"ILGUS BHAVAN"

H-C BLOCK, SECTOR-III, BIDHANNAGAR, CALCUTTA-700 091
West Bengal

Ref No. SUDA-63-ULBs/20(Pt. I)/08/347

Date02.01.2009

From : Director, SUDA

To : The Chairman
Tamluk Municipality

Sub. : Repair work of 3 SCs under Community Based
Primary Health Care Services.

Sir,

Reference is invited to your communication bearing memo no. 21/Health/TM dt. 17.07.2008 on the above mentioned subject.

You are requested to furnish the necessary drawings and quoted rates as per PWD schedule. You may contact Sri Biswajit Das, TUO, SUDA in this regard, if needed.

Thanking you.

Yours faithfully,

o/c

Director, SUDA

SUDA-63 ULBs/20(Pt. I)/08/347/1(1)

Dt. .. 02.01.2009

CC

Shri Biswajit Das, TUO, SUDA

Director, SUDA

তমলুক পৌরসভা

OFFICE OF THE COUNCILLORS OF TAMLUK MUNICIPALITY

স্থাপিত - ১৮৬৪ ★ Estd.- 1864

তমলুক, পূর্ব মেদিনীপুর - ৭২১৬৩৬ ★ TAMLUK, PURBA MEDINIPUR - 721636

Phone : (03228) 266007 / 267370 / 269537, Fax - (03228) 267370

প্রেরক From :

পৌরপ্রধান Chairman

তমলুক পৌরসভা

Tamluk Municipality



স্মারক / পত্রাক নং Memo No. 21/Health/T.M

তারিখ, তমলুক,

Dated, Tamluk, The.....

প্রতি To :

To
The Director
State Urban Development Agency
(Health Wings)
ILGUS Bhavan
HC-Block, Sector -III, Bidhannagar
Kolkata - 700 091



Sub: Prayer for approval of the repairing work of 3 Sub Center under Community Based Primary Health Care Services.

Madam,

I would like to draw your kind attention that we have already opened 5th sub centers under Community Based Primary Health Care Services, out of the above 5th Sub Centers in 3 sub centers we have already done some repairing work before opening the sub center. In this regard we are to send herewith the estimate cost for your approval.

Yours truly,

Enclosure: As stated above.



P. N. Nandy
17/11/17

(P. N. Nandy)
Chairman
Tamluk Municipality

Tamluk Municipality

TAMLUK MUNICIPALITY
TAMLUK * PURBA MEDINIPUR

DETAIL MEASUREMENTS AND CALCULATIONS

Detailed Estimate No. for the year 200 - 200

Name of work... *Repairing of store room of Health dept. at C.D.S. Hall*
of U.C. Samkaraka in W.P. No. 21

Sl. No	DESCRIPTION OF WORK	No.	Length	Total Length	Breadth	Height or Depth	Content or Area	Total	GRAND-TOTAL
1.	M.S. Ornamental grill --- above 16 kg/m ² and above.								
				$1 \times 1.10 \times 2.10 \times 22 \text{ kg/m}^2 = 50.82 \text{ kg}$			$50.82 \text{ kg} @ 36 \text{ paise}$		1829.52
2.	Extra for work in grill gate. 15% of item no-①							R ₁	274.35
3.	Labour charges for removal of old door & refixing the same		L.S.					R ₁	750.00
4.	Painting of grill by Synthetic paint including priming coat. 20% + 28%						$1.10 \times 2.10 = 2.31 \text{ m}^2 @ 58 \text{ paise}$	R ₁	133.98
5.	Material cost of finish of grill gate.		L.S.					R ₁	250.00
								R ₁	3237.85
							Add 3% contingencies	R ₁	97.14
									3334.99
								Say R ₁	3335

B. P. A. S.
SUB ASSISTANT ENGINEER
TAMLUK MUNICIPALITY

1
30
50

TAMLUK MUNICIPALITY
TAMLUK * PURBA MEDINIPUR

DETAIL MEASUREMENTS AND CALCULATIONS

Detailed Estimate No. for the year 200 - 200
 Name of work... Making partition wall of Room at Chakkamins C.D.S.
 Hall in ward no :- 22.

DESCRIPTION OF WORK	No.	Length	Total Length	Breadth	Height or Depth	Content or Area	Total	GRAND TOTAL
Wood work in posts, plates, rafters, battens, truss members, purlins etc. fitted and fixed complete. (ii) <u>Local</u>	1	138'0"		2'4"	1 1/2' = 2.675ft.	= 0.075 cu.m	@ Rs 18,604/- = Rs 1395.30	
Partition of commercial ply as per design fitted and fixed complete. (i) <u>4mm thick</u>	1	18'2"			7'10" = 142.37 sqft	= 13.28 sqm	@ Rs 222/- = Rs 2937.05	
Priming one coat on timber, plastered surface with synthetic enamel of approved quality including smoothing surfaces by sandpapering etc.			13.23 sqm			@ Rs 20/-	= Rs 264.60	
 <i>(Signature)</i>							Rs 4596.95	

TAMLUK MUNICIPALITY

TAMLUK * PURBA MEDINIPUR

DETAIL MEASUREMENTS AND CALCULATIONS

Detailed Estimate No. for the year 200 - 200

Name of work... Repairing works of a room and verandah in the Mosque premises - at mouza :- Padumbasan, in ward no:-7 under Tamaluk Municipality.

Sl. No	DESCRIPTION OF WORK	No.	Length	Total Length	Breadth	Height or Depth	Content or Area	Total	GRAND TOTAL
1.	Artificial Stone in floor, dado, staircase etc. with cement concrete (4:2:1) with stone chips, laid in panels as directed with topping made with ordinary or white cement and marble dust in proportion (2:1) including smooth finishing. 3mm. thick topping with ordinary cement. (i) 25 mm. thick.								
	<u>Verandah</u>	1	22' 5"		5' 0"		= 128.01 sqft.		
	<u>Room</u>	1	16' 8"		(13' 2" + 7' 7") / 2		= 206.08 sqft.		
							334.09 sqft.		
							= 31.13 sqm.		
							@ Rs 124/-	= Rs 3922.40	
2.	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners. (i) With 4:1 cement mortar @ 25 mm thick inside wall plaster.								
		1	16' 8"			6' 0"	= 99.96 sqft.		
		1	13' 2"			6' 0"	= 78.96 sqft.		
							178.92 sqft.		
							= 16.63 sqm.		
							@ Rs 58/-	= Rs 964.55	
									Rs 4886.95

P. S. Banerjee
 P. S. Banerjee
 P. S. Banerjee Engineer,
 Tamaluk Municipality.