

**SUDA**

# STATE URBAN DEVELOPMENT AGENCY

HEALTH WING  
"ILGUS BHAVAN"

H-C BLOCK, SECTOR-III, BIDHANNAGAR, CALCUTTA-700 091  
West Bengal

Ref No. ....SUDA-Health/527/09/383

Date .....24.01.2011

From : Director, SUDA

To : Shri D.K. Ghosh, IAS  
Commissioner, Family Welfare &  
Spl. Secretary  
Dept. of Health Family Welfare

Sub. : Submission of Utilisation Certificate.

Ref. : Communication of DHFW bearing no. HFW/HSDI/230/HHW-193/06  
dt. April 24, 2008.

Sir,

Enclosed kindly find herewith Utilisation Certificate (UC) in respect of fund released towards construction of one portion of the Annexed Hospital Building of the Maternity & Child Welfare centre under Joynagar Mazilpur Municipality, South 24 Parganas.

Thanking you.

Yours faithfully,

Encl. : (1) Communication of DHFW.  
(2) Utilisation Certificate.

*SLR*

Director, SUDA

SUDA-Health/527/09/383/1(2)

Dt. .. 24.01.2011

CC

1. Dr. J. Chaki, Jt. DHS & SFWO, DHFW.
2. OSD, HSDI, DHFW

*J. Goswami*  
Director, SUDA

23530141

GOVERNMENT OF WEST BENGAL  
DEPARTMENT OF HEALTH & FAMILY WELFARE  
HEALTH SYSTEM DEVELOPMENT INITIATIVE  
SWASTHYA BHAVAN, GN-29, SECTOR-V  
SALT LAKE CITY, KOLKATA - 700 091  
TEL: 2357 4455

No.HFW/HSDI/230/HHW-193/06

April 24, 2008

**From: A. K. Das, IAS**  
Project Director, HSDI,  
Commissioner, Family Welfare & Special Secretary

**To: Dr. Shibani Goswami,**  
Project Officer, Health, SUDA,  
Ilgus Bhavan  
Block-HC, Sector-III,  
Bidhan Nagar,  
Salt Lake, Kolkata - 700091.

**Sub:** Release of fund for construction of one portion of the Annexed Hospital Building of the Maternity and Child Welfare Centre under Joynagar Mazilpur Municipality, South 24 Parganas.

Madam,

In inviting reference to your letter no. SUDA/Health/63/ULBs/07/764 dated 19.03.2008 this is to inform you that a sum of Rs. 8,13,592 (Rupees eight lakh thirteen thousand five hundred ninety two) only is hereby released in your favour for meeting the non-recurring expenditure towards construction of one portion of the Annexed Hospital Building of Maternity & Child Welfare Centre under Joynagar Mazilpur Municipality, South 24 Parganas as per plan and estimate prepared by the Sub-Assistant Engineer, Joynagar Mazilpur Municipality and approved by the Executive Engineer, HSDI on behalf of this Department.

The Joint Director (Accounts), HSDI will act as the Drawing and Disbursing Officer for the purpose.

The charge is debitable to the head of Account under "Grants-in-Aid" provision of HSDI Fund from the budgetary allocation for the year 2008-09.

It may be noted that the fund so released should be strictly used for the purpose mentioned above. Copy of the plan and estimate in respect of the work are being returned herewith for execution.

The Utilisation Certificate duly supported by the Statement of Expenditure in respect of the fund should be submitted to the undersigned immediately as soon as the expenditure is incurred and latest by 31<sup>st</sup> December, 2008.

This order is issued under the authority of power delegated to the Additional Chief Secretary of Health and Family Welfare Department, Government of West Bengal under Finance Department's Memo No. 10637-F dated 23.12.2005.

You are requested to kindly send your authorized representative to collect the cheque from the Accountant, HSDI at Swasthya Bhavan, Salt Lake, Kolkata.

Yours faithfully,



(A. K. Das)

Project Director, HSDI, Commissioner, F.W.,  
& Special Secretary

**Utilisation Certificate**  
(Form No. S.R. 330 A)

Sl. No.	Ch. No. & Date	Amount (in Rs.)
1.	Ch. No. 020225 dt. 05.05.2008 United Bank of India, Salt Lake Branch, Sector - V vide GO No. HFW/HSDI/230/HHW-193/06 dt. 24 <sup>th</sup> April, 2008	8,13,592.00
	<b>Total</b>	

Certified that out of Rs. 8,13,592/- of Grants-in-aid sanctioned during the year 2008-09 in favour of Director, SUDA towards construction of one portion of the Annexed Hospital Building of the Maternity & Child Welfare centre under Joynagar Mazilpur Municipality, South 24

Parganas under this Ministry / Department letter no. given in the margin and a sum of Rs. 8,13,592/- has been utilized for the purpose it was sanctioned.

Certified that I have satisfied myself that the conditions on which the Grant-in-aid was sanctioned has been duly fulfilled / ~~are being fulfilled~~ and that I have exercised the checks to see that the money was actually utilized for the purpose for which it was sanctioned.

Dr. S. GOSWAMI

Project Office  
Health Wing

S. U. D. A

f Signature of Director, SUDA

24-07-2011  
DIRANKAR CHOWDHURY

Phone No. 03218 – 220210

Fax No. 03218 – 221044

# JOYNAGAR MAJILPUR MUNICIPALITY

P.O. Jaynagar Majilpur. South 24parganas

PIN - 743337

Memo No. JMM/ XII - (2) / Dev / 350  
From  
The Chairman/Vice-Chairman  
Joynagar Mojilpur Municipality

Dated:- 26.10.10.

To  
The Director  
SUDA,  
ILGUS Bhavan,  
H.C Block, Sector-III, Salt Lake,  
Kolkata -700106,



Sub:- Fund support for construction of one portion of the annexed  
Hospital building of maternity & Child Welfare Center, Joynagar  
Mozilpur municipality.

Ref-Your no SUDA/Health/60/08/184 dated 18/08/2010.

Sir,

With reference to above detailed structural drawing and estimate, as desired, are submitted here with for your kind perusal & necessary action.

In this connection it may be mentioned that in response to our proposal dated 22/01/2008 an amount of Rs.813592.00 was earlier sanctioned and released vide your no SUDA/Health/63/ULBS/Acet//08/125 dated 30/06/2010 The balance amount may kindly be sanctioned and released at the earliest.

Delay of submission of desired drawing and estimated for unavoidable reason may kindly condoned.

Thanking you.

Enclosed:-

- 1) Structural Drawing 2 Copies.
- 2) Estimate 2 Copies.



Yours faithfully,

*J. S. Haikh*  
26.10.10.

CHAIRPERSON

Joynagar Mojilpur Municipality

JOYNAGAR MOZILPUR MUNICIPALITY

SOUTH 24 PARGANAS

## ESTIMATE FOR CONSTRUCTION OF HOSPITAL BUILDING (m.c.w.c)

### AT JOYNAGAR MOJILPUR MUNICIPALITY, SOUTH -24 PARGANAS

Sl. No.	Description of Work	Quantity	Unit	Rate	Amount
1	<b>Earth work in excavation</b> of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sand stone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, leveling, dressing and ramming the bottom, bailing out water etc. as required complete.				
	Depth of excavation not exceeding 1,500 mm.	146.25	%cu.m.	4187.00	6123.49
2	<b>Earth work in filling in foundation trenches</b> or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete.				
	a) With earth obtained from excavation of foundation	30	%cu.m.	2600.00	780.00
3	<b>Filling in foundation or Plinth by silver sand</b> in layers not exceeding 150 mm. as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand.				
		92.2	%cu.m.	27050.00	24940.10
4	Supplying and laying <b>Polythene Sheet</b> (150 gm/sq.m.) over damp proof course or below flooring or roof terracing or in foundation trenches				
		170	sq.m.	10.00	1700.00
5	<b>Cement concrete with graded stone ballast</b> (40 mm. Size) excluding shuttering. In ground floor				
	6 : 3 : 1 Proportion	20.13	cu.m.	3195.45	64324.41
6	Ordinary Cement conc.(3:1.5:1) <b>M-20 Cement concrete</b> with graded <b>stone chips</b> (20mm size) excluding shuttering and reinforcement, If any. In ground floor. Pakur/Chandil Variety				
	a) In ground floor.	80	cu.m.	4547.00	363760.00
7	<b>Reinforcement</b> for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc. including supply of rods, initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in roper position and binding with 16 gauge black annealed wire at every inter-section, complete as per drawing and direction.				
	For works in foundation, basement and upto roof of ground floor/upto 4 m. Tor steel / Mild steel				
	a) In ground floor	7.92	MT	40000.00	316800.00
8	Hire and labour charges for <b>shuttering</b> with centreing and necessary staging upto 4 m. using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams, columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor)				
	i) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-in-charge.				
	a) In Ground floor.	486	sq.m.	160.00	77760.00
	iii) 25mm to 30mm shuttering without staging in foundation etc.				
9	<b>Brick work with 1st class bricks in cement mortar ( 6 : 1)</b>				
	a) In foundation and plinth	20	cu.m.	2961.00	59220.00
	b) In superstructure	52.77	cu.m.	3048.00	160842.96
	i) In Ground floor.				

Sl. No.	Description of Work	Quantity	Unit	Rate	Amount
10	<b>Artificial stone in floor</b> dado, staircases etc. with cement concrete (4:2:10 with stone chips, laid in panels as directed with topping made with ordinary/white dust in proportion (2 : 1) including smooth finishing and rounding off corners & including application of cement slurry before flooring works, using cement 1.75 %kg/sq.m. all complete including all materials & labour.	148	sq.m	141.00	20868.00
11	Single brick Flat Solling picked Jhama bricks ———and filling joints with powdered earth or-local sand,	182	sqm	161.00	29302.00
12	<b>Plaster</b> (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chipping corners as directed and raking out joints or roughening of concrete surface by chamfering etc. including throating, nosing and drip course where necessary (Ground floor) :				
A) a)	in ground floor				
	With 6 : 1 sand cement mortar				
	ii) 15 mm thick plaster	380	sq.m.	80.00	30400.00
	iii) 20 mm Thick plaster	330	sq.m.	92.00	30360.00
B)	With 4 : 1 sand cement mortar				
	ii) 10 mm thick plaster	171	sq.m.	73.00	12483.00
13	<b>Neat cement</b> punning average 1.5 mm thick in wall, dado, window, sills floor, drain etc.				
	a) In ground floor	160	sq.m.	19.00	3040.00
14	<b>Collapsible gate</b> with 40 mm X 40 mm X 6 mm tee as top and bottom guide rail 20 mm X 10 mm X 2 mm vertical channel apart in fully stretched position 20 mm X 5 mm M.S. flats as collapsible bracings properly rivetted and washered including 38 mm steel rollers including locking arrangements, fitted and fixed in position with lugs set in cement concrete and including cutting necessary holes, chasing etc in walls, floors etc and making good damages complete.				
	in ground floor	6	sq.m..	2281.00	13686.00
15	<b>Wood work</b> in door and window frame fitted and fixed complete including a protective coat of painting at the contact surface of the frame.				
	Sal : Siliguri				
16	<b>M.S. clamp</b> for fixing door and window frame made of flat bent bar, end bifurcated, fixed in cement concrete with stone chips (4 : 2 : 1) 40 mm X 6 mm above 250 mm upto 350 mm length	0.43	cum	47209.80	20300.20
17	a) Glazed shutters of door, windows, etc as per design--- fitted with putty bed and teak wood bead and nails including--- fitting and fixing shutter in position but excluding the cost--	56	each	38.00	2128.00
	<b>25mm thick shutter. Sal; siliguri,</b>	21.5	Sqm	2231.90	47985.85
18	<b>M. S. integrated grill</b> as per approved desig integrated with steel window or ventilator, joints continuously welded with M. S. flats and bars.	167	kg.	56.00	10472.00
	i) <b>Two point nose aluminium handle</b> including fitting and fixing	18	each	21.00	378.00
	ii) <b>aluminium peg stay</b> 300 mm. long includng fitting ad fixing.	18	each	23.00	414.00



Sl. No.	Description of Work	Quantity	Unit	Rate	Amount
19	Painting on timber, plaster or steel or other metal surface--- with synthetic enamel/oil bound primer of approved quality	49	sqm	38.00	1862.00
20	Clour washing with any shade with stainers.asrequired incl-- ding cleaning and smoothening surface thoroughly : a) two coat other than yellow, pink	881	%Sqm	920.00	8105.00
				Total= Rs	1308035.01
				Say =Rs	1308035.00
				add 1% cess	13080.35
				3% contingency	39241.05
				Say =Rs	1360356.40
				Say =Rs	1360356.00
a)					

*Sammiti*

Sub- Assistant Engineer  
Joynagar Mozilpur Municipality  
South 24 Parganas

*Jaynagar*  
13.12.10.  
Chairperson  
Jaynagar-Majilpur  
Municipality

# JOYNAGAR MOZILPUR MUNICIPALITY

SOUTH 24 PARGANAS

## ESTIMATE FOR CONSTRUCTION OF HOSPITAL BUILDING (m.c.w.c)

### AT JOYNAGAR MOJILPUR MUNICIPALITY, SOUTH -24 PARGANAS

Sl. No.	Description of Work	Quantity	Unit	Rate	Amount
1	<b>Earth work in excavation</b> of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sand stone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, leveling, dressing and ramming the bottom, bailing out water etc. as required complete.				
	Depth of excavation not exceeding 1,500 mm.	146.25	%cu.m.	4187.00	6123.49
2	<b>Earth work in filling in foundation trenches</b> or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete.				
	a) With earth obtained from excavation of foundation	30	%cu.m.	2600.00	780.00
3	<b>Filling in foundation or Plinth by silver sand</b> in layers not exceeding 150 mm. as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand.	92.2	%cu.m.	27050.00	24940.10
4	Supplying and laying <b>Polythene Sheet</b> (150 gm/sq.m.) over damp proof course or below flooring or roof terracing or in foundation trenches	170	sq.m.	10.00	1700.00
5	<b>Cement concrete with graded stone ballast</b> (40 mm. Size) excluding shuttering. In ground floor				
	6 : 3 : 1 Proportion	20.13	cu.m.	3195.45	64324.41
6	Ordinary Cement conc.(3:1.5:1) <b>M-20 Cement concrete</b> with graded <b>stone chips</b> (20mm size) excluding shuttering and reinforcement, if any. In ground floor. Pakur/Chandil Variety				
	a) In ground floor.	80	cu.m.	4547.00	363760.00
7	<b>Reinforcement</b> for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc. including supply of rods, initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in roper position and binding with 16 gauge black annealed wire at every inter-section, complete as per drawing and direction.				
	For works in foundation, basement and upto roof of ground floor/upto 4 m. Tor steel / Mild steel				
	a) In ground floor	7.92	MT	40000.00	316800.00
8	Hire and labour charges for <b>shuttering</b> with centreing and necessary staging upto 4 m. using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams, columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor)				
	i) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-in-charge.				
	a) In Ground floor.	486	sq.m.	160.00	77760.00
	iii) 25mm to 30mm shuttering without staging in foundation etc.				
9	<b>Brick work</b> with 1st class bricks in cement mortar ( 6 : 1)				
	a) In foundation and plinth	20	cu.m.	2961.00	59220.00
	b) In superstructure	52.77	cu.m.	3048.00	160842.96
	j) In Ground floor.				

Sl. No.	Description of Work	Quantity	Unit	Rate	Amount
10	<b>Artificial stone in floor</b> dado, staircases etc. with cement concrete (4:2:10 with stone chips, laid in panels as directed with topping made with ordinary/white dust in proportion (2 :1) including smooth finishing and rounding off corners & including application of cement slurry before flooring works, using cement 1.75 %kg/sq.m. all complete including all materials & labour.	148	sq.m	141.00	20868.00
11	Single brick Flat Solling picked Jhama bricks ——— and filling joints with powdered earth or-local sand,	182	sqm	161.00	29302.00
12	<b>Plaster</b> (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chipping corners as directed and raking out joints or roughening of concrete surface by chamfering etc. including throating, nosing and drip course where necessary (Ground floor) :				
A) a)	In ground floor				
	With 6 : 1 sand cement mortar				
	ii) 15 mm thick plaster	380	sq.m.	80.00	30400.00
	iii) 20 mm Thick plaster	330	sq.m.	92.00	30360.00
B)	With 4 : 1 sand cement mortar				
	ii) 10 mm thick plaster	171	sq.m.	73.00	12483.00
13	<b>Neat cement</b> punning average 1.5 mm thick in wall, dado, window, sills floor, drain etc.				
a)	In ground floor	160	sq.m.	19.00	3040.00
14	<b>Collapsible gate</b> with 40 mm X 40 mm X 6 mm tee as top and bottom guide rail 20 mm X 10 mm X 2 mm vertical channel apart in fully stretched position 20 mm X 5 mm M.S. flats as collapsible bracings properly rivetted and washered including 38 mm steel rollers including locking arrangements, fitted and fixed in position with lugs set in cement concrete and including cutting necessary holes, chasing etc in walls, floors etc and making good damages complete.				
	in ground floor	6	sq.m..	2281.00	13686.00
15	<b>Wood work</b> in door and window frame fitted and fixed complete including a protective coat of painting at the contact surface of the frame.				
	Sal : Siliguri				
16	<b>M.S. clamp</b> for fixing door and window frame made of flat bent bar, end bifurcated, fixed in cement concrete with stone chips (4 : 2 : 1) 40 mm X 6 mm above 250 mm upto 350 mm length	0.43	cum	47209.80	20300.20
17 a)	Glazed shutters of door, windows, etc as per design---- fitted with putty bed and teak wood bead and nails including---- fitting and fixing shutter in position but excluding the cost--	56	each	38.00	2128.00
	<b>25mm thick shutter. Sal; siliguri,</b>	21.5	Sqm	2231.90	47985.85
18	<b>M. S. integrated grill</b> as per approved desig integrated with steel window or ventilator, joints continuously welded with M. S. flats and bars.	187	kg.	56.00	10472.00
i)	<b>Two point nose aluminium handle</b> including fitting and fixing	18	each	21.00	378.00
ii)	<b>aluminium peg stay</b> 300 mm. long including fitting ad fixing.	18	each	23.00	414.00

Sl. No.	Description of Work	Quantity	Unit	Rate	Amount
19	Painting on timber, plaster or steel or other metal surface— with synthetic enamel/oil bound primer of approved quality	49	sqm	38.00	1862.00
20	Clour washing with any shade with stainers.asrequired incl— ding cleaning and smoothening surface thoroughly : a) two coat other than yellow, pink	881	%Sqm	920.00	8105.00
				Total= Rs	1308035.01
				Say =Rs	1308035.00
				add 1% cess	13080.35
				3% contingency	39241.05
				Say =Rs	1360356.40
a)					

  
Sub- Assistant Engineer  
Joynagar Mozilpur Municipality  
South 24 Parganas ✓

  
13.12.10.  
Chairperson  
Jaynagar-Majilpur  
Municipality

**STATE URBAN DEVELOPMENT AGENCY****HEALTH WING****"ILGUS BHAVAN"****H-C BLOCK, SECTOR-III, BIDHANNAGAR, CALCUTTA-700 091  
West Bengal**Ref No. **SUDA-Health/60/08/184**Date **18.08.2010****From : Director, SUDA****To : The Chairman  
Jaynagar Mazilpur Municipality****Sub. : Fund support for construction of one portion of the Annexed Hospital building of Maternity & Child Welfare Centre under Jaynagar Mazilpur Municipality, South 24 Parganas.****Sir,**


I am to refer to this office earlier communication vide no. SUDA-Health/63 ULBs/Accts./08/125 dt. 30.06.2008 on the subject mentioned above (copy enclosed for ready reference).

You may be aware that Shri S.K. Banerjee, OSD, SUDA & Retd. Asstt. Engineer of MED visited your ULB on 22.06.2010 to supervise the said construction work. In this connection, you are requested to submit a detailed structural drawing and estimates by 30.08.2010 for taking further necessary action by this end.

Thanking you.

Encl: AS stated

Yours faithfully,

  
Director, SUDA

सूडा

SUDA

DIRECTOR,  
SUDA.

Inspection report in respect of work "Hospital Building (M.C.W.C)" with in Jyotnagar Mazilpore Municipality is placed to the Director SUDA along with drawing and xerox copy of bill, for information and further necessary action please

Somn Kumar Banerjee  
28/6/2010

H. A  
Pl. put up  
①  
29/6

## TOUR REPORT

As directed by the Director, SUDA, I have visited Joy nagar Mazitpur Municipality <sup>on 22.6.2016</sup> to inspect the work done by the Municipality for the work construction of Hospital Building. (M.C.W.C) with in Joy nagar Mazitpur Municipality

The following observations are noted below for further necessary action.

- i) The Municipality has furnished a drawing which is not proper (drawing enclosed)
- ii) The Municipality has deviated the site plan i.e instead of two places ULB has executed the building in one place.
- iii) The Municipality has executed the work departmentally but maintained Measurement Book and prepared bill for payment (Xerox copy of bill enclosed)
- iv) The covered area of the building approx 190 Sqr including staircase, consisting 18 nos of columns as mentioned in the estimate submitted by the Municipality
- v) The work done by the Municipality is apparently satisfactory except the hidden portion (i.e foundation) which is not possible to verify at present.

The Municipality may kindly be asked to submit detailed structural drawing and estimates for taking further necessary action from this end.

This is placed to Director SUDA for information and further necessary action please.

Suman Kumar Dasgupta  
28/6/2016



# JOYNAGAR-MOZILPUR MUNICIPALITY

P. O. JOYNAGAR-MOZILPUR,

Dist. 24-Parganas.

743337

Form No. 57

(Vide rule 157)

*work in progress*  
**CONTRACT CERTIFICATE**

Authority for work

Name of work Development of M.C.W.C. hospital Building of J.M. Municipality in U-IX  
Name of contractor Departmental work

No. of this certificate

Unit	Quantity executed or supplied since last certificate	Quantity executed or supplied up to date as per measurements	Items	Rate	AMOUNT		REMARKS (In the case of supplies the name of the receiving officers should be entered here)
					Up to date	Since last certificate	
1	2	3	4	5	6	7	8
<del>7m<sup>3</sup></del>	<del>135.0</del>	<del>135.0</del>	<del>E/W in excavation.</del>	<del>41.87</del>	<del>5652.48</del>		
<del>m<sup>3</sup></del>	<del>27.0</del>	<del>27.0</del>	<del>E/W in filling.</del>	<del>26.00</del>	<del>702.00</del>		
<del>m<sup>2</sup></del>	<del>113.0</del>	<del>113.0</del>	<del>S.B.F.S.</del>	<del>161.00</del>	<del>18193.00</del>		
<del>m<sup>3</sup></del>	<del>97.2</del>	<del>97.2</del>	<del>Silver sand filling.</del>	<del>270.50</del>	<del>26292.00</del>		
<del>m<sup>3</sup></del>	<del>16.87</del>	<del>16.87</del>	<del>Cement concrete with ghuma (1:3:6)</del>	<del>2748.60</del>	<del>46368.88</del>		
<del>m<sup>2</sup></del>	<del>186.0</del>	<del>186.0</del>	<del>Shuttering (hire &amp; labour charge)</del>	<del>159.50</del>	<del>77517.00</del>		
<del>m<sup>3</sup></del>	<del>78.50</del>	<del>78.50</del>	<del>Ordinary cement concrete (1:1.5:3)</del>	<del>4546.80</del>	<del>356923.80</del>		
<del>MT</del>	<del>7.972</del>	<del>7.972</del>	<del>Reinforcement</del>	<del>40000.00</del>	<del>318880.00</del>		
<del>m<sup>3</sup></del>	<del>20.00</del>	<del>20.00</del>	<del>25cm thick B/W (1:1:6)</del>	<del>3047.80</del>	<del>60956.00</del>		
					<del>Rs. 911485.73</del>		
					<del>Say Rs. 911486.00</del>		
<del>Address Only</del> (Rupees Nine lakh eleven thousand four hundred & eighty six only.)							
			Total value of work done or supplies made to date				
			Deduct value of work or supplies shown on last certificate				
			Net value of work done or supplies made since last certificate				

Contractor.

Certified that the necessary detailed measurements have been taken by me on the 16/09/2009 and are recorded at page 1627 of my measurement book No. DEV/BW/2008-09/1.

Dated the

[Signature]  
Overseer or officer in charge of the work.

Certified that I have examined the work and that I have satisfied myself to the best of my ability that it has been carried out in accordance with the sanctioned plans and estimates.

[Signature]  
Vice-Chairman, Secretary or Ward Commissioner.

Certified that the work was materials were duly check measured by me on (date )

[Signature]  
Vice-Chairman, Secretary or Ward Commissioner.

If the work is not check measured, the last certificate may be scored out.

# MEMORANDUM OF PAYMENTS MADE

Total value of work done ... *Departmental work (in progress)* ...

Amount of previous payments from last certificate No. ... of ...

	Rs.	P.	Rs.	P.
Payments now made	...	...	...	...
By cash	...	...	...	...
By cheque No. ...	...	...	...	...
By value of stock-supplied	...	...	...	...
<i>Balance due</i>	911488			

Received Rs. *911488* only, as per details above, on account of this work.

*[Signature]*  
 Chairman  
 Joy Nagar Mallipuram  
 Municipality

STAMP

Dated the *91* Contractor

Witnesses { \_\_\_\_\_



As directed by the Director S.U.D.A I have visited Jaynagar - Hazilpur Municipality on 22.6.10 to inspect the Hospital Building (M.C.W.) and a tour report has been submitted on 28.6.10. It is reported that the said report is not available. However I am resubmitting the said report in xerox along with xerox copy of bill as received from the municipality. This is placed to the Director S.U.D.A for taking further necessary action please.

Somen Kumar Bhandari  
13.8.2010

DIRECTOR  
SUDA.

PO (H)  
✓  
13/8  
FO (H)  
16.8.10

## TOUR REPORT

As desired by the Director SUDA I have visited Joyragar Mazitpur Municipality <sup>on 22.6.20</sup> to inspect the work done by the Municipality for the work construction of Hospital Building. (M.C.W.C) with in Joyragar Mazitpur Municipality

- The following observations are noted below for further necessary action.
- i) The Municipality has furnished a drawing which is not proper (drawing enclosed)
- ii) The Municipality has deviated the site plan i.e. instead of two places ULB has executed the building in one place.
- iii) The Municipality has executed the work departmentally but maintained Measurement Book and prepared bill for payment (Xerox copy of bill enclosed)
- iv) The covered area of the building approx 190 Sqm including staircase, consisting 18 no. of columns as mentioned in the estimate submitted by the Municipality
- v) The work done by the Municipality is apparently satisfactory except the hidden portion (i.e. foundation) which is not possible to verify at present.

The Municipality may kindly be asked to submit detailed structural drawing and estimates for taking further necessary action from this end.

This is placed to Director SUDA for intervention and further necessary action please.

Somn Kumar  
20/06/2010

# JOYNAGAR-MOZILPUR MUNICIPALITY

P. O. JOYNAGAR-MOZILPUR,

Dist. 24-Parganas.

743337

Form No. 57

(Vide rule 157)

*work in progress*  
**CONTRACT CERTIFICATE**

Authority for work

Name of work

Name of contractor

No. of this certificate

Chairman Joynagar Mozilpur Municipality

*Development of M.C.W.C. hospital Building of J.M. Municipality W.U. IX*  
*Departmental work*

Unit	Quantity executed or supplied since last certificate	Quantity executed or supplied up to date as per measurements	Items	Rate	AMOUNT		REMARKS (In the case of supplies the name of the receiving officers should be entered here)
					Up to date	Since last certificate	
1	2	3	4	5	6	7	8
<del>cu 3</del>	<del>135.0</del>	<del>135.0</del>	<del>E/W excavation</del>	<del>41.87</del>	<del>5652.45</del>		
<del>cu 3</del>	<del>27.0</del>	<del>27.0</del>	<del>Earth filling</del>	<del>26.00</del>	<del>702.00</del>		
<del>cu 2</del>	<del>113.0</del>	<del>113.0</del>	<del>S.B.F.S.</del>	<del>161.00</del>	<del>18193.00</del>		
<del>cu 3</del>	<del>97.2</del>	<del>97.2</del>	<del>Silver sand filling</del>	<del>270.50</del>	<del>26292.60</del>		
<del>cu 3</del>	<del>16.87</del>	<del>16.87</del>	<del>Cement concrete with ghuma (1:3:6)</del>	<del>2748.60</del>	<del>46388.88</del>		
<del>cu 2</del>	<del>186.0</del>	<del>186.0</del>	<del>Shuttering (hire &amp; labour charge)</del>	<del>159.50</del>	<del>77517.00</del>		
<del>cu 3</del>	<del>78.50</del>	<del>78.50</del>	<del>Ordinary cement concrete (1:1.5:3)</del>	<del>4546.80</del>	<del>356923.80</del>		
<del>MT</del>	<del>7.972</del>	<del>7.972</del>	<del>Reinforcement</del>	<del>40000.00</del>	<del>318880.00</del>		
<del>cu 3</del>	<del>20.00</del>	<del>20.00</del>	<del>250mmth. B/W (1:1:6)</del>	<del>3047.80</del>	<del>60956.00</del>		
					<del>Rs. 711485.73</del>		
					<del>say Rs. 711486.00</del>		
<del>Add extra Amty (Rupees Nine lakh eleven thousand four hundred &amp; eighty six only.)</del>							
Total value of work done or supplies made to date							
Deduct value of work or supplies shown on last certificate							
Net value of work done or supplies made since last certificate							

Contractor.

Certified that the necessary detailed measurements have been taken by me on the 16<sup>th</sup> 09-2009  
19 and are recorded at page 1627 of my measurement book No. DEV/6W/2008-09/1.

Dated the

*Overseer or officer in charge of the work.*

Certified that I have examined the work and that I have satisfied myself to the best of my ability that it has been carried out in accordance with the sanctioned plans and estimates.

*Vice-Chairman, Secretary or Ward Commissioner.*

Certified that the <sup>work was</sup> materials were duly check measured by me on (date )

*Vice-Chairman, Secretary or Ward Commissioner.*

If the work is not check measured, the last certificate may be scored out.

# MEMORANDUM OF PAYMENTS MADE

Total value of work done *Departmental work (in progress)*

Rs. P.

Amount of previous payments from last certificate No. *911488* of *...*

Rs. P.

Payments now made {  
 By cash *...*  
 " cheque No. *...*  
 " value of stock-supplied *...*

*Bill raised for Rs. 911488 - (Surplus in my bank account transferred for credit of m.c.w. 4/1/54)*  
*Rs. 1000/-*  
*Balance due 911486*

only, as per details above, on account of this work.

*[Signature]*

Chairman  
 Joyangar Municipality

STAMP

Dated the *91*

Contractor

Witnesses {

Phone No. 03218 - 220210

Fax No. 03218 - 221044

**JOYNAGAR MOJILPUR MUNICIPALITY**

**P.O. Jaynagar Majilpur. South 24parganas**

**PIN - 743337**

FO.  
11.03.10

Memo No. J.M.H/M.E.W.E/656.

Dated:- 08.03.10.

From  
The Chairman/Vice-Chairman  
Joynagar Mojilpur Municipality

To  
The Director,  
SUDA, ILGUS Bhavan,  
H.C Block, Sector III  
Bidhannagar, Kolkata - 700 106.



Sub:- Submission of Estimate for the work "Construction of Hospital building" (M.C.W.C) under Joynagar Mojilpur Municipality.

Sir,

I am submitting herewith the estimate of Rs. 9,67,259.00(Nine lakhs sixty seven thousand two hundred fifty nine)out of which Rs. 8,13,592.00(Eight lakhs thirteen thousand five hundred ninety two) has been sanctioned. for "Construction of hospital building (M.C.W.C)" within which only the roof casting along with column, roof-beam, tie-beam, has been completed.

I would therefore request you to sanction a further allotment of Rs.6,00,000.00 (approximately) at an early date as we can complete the building.

Thanking you.

Your's faithfully

CHAIRMAN

Joynagar Mojilpur Municipality




**Proposed Estimated for Construction of hospital building ( M.C.W.C. ),  
under Joynagar Mozilpur Municipality, 24-Parganas ( South )**

NO.	Description of Items	Quantity	Unit	Rate	Amount
1	Earth work in excavation of foundation trenches or drains, in all sorts of soil ( including mixed soil but excluding laterite or sand stone) including removing, spreading or stacking the spils within a lead of 75m as direct, the itme include necessary trimming the sides of trenches, leveling dressing and ramming the bottom. Bailing out water as recuried complete (a) Depth of excavation not exceeding 1500mm	135m3	% m <sup>3</sup>	4187.00	5652.45
2	Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150mm including watering and raming etc. layer by layer by complete. (Payment to be made on basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation	27m3	m <sup>3</sup>	26.00	702.00
3	Single brick flat soiling of picker jhama bricks including ramming and dressing bed to proper level, and filling joints with powdered earth or local sand.	113m2	m <sup>2</sup>	161.00	18193.00
4	Cement concrete (with graded jhama khoa (30mm. Down size) Excluding shuttering in ground floor and foundation. (a) 6:3:1 Proportion.	16.86m3	m <sup>3</sup>	2748.60	46341.39
5	Hire and labour charges for shuttering with centering and necessary stageing up to 4m using approved stout props and thick hard wood planks of approved thickness with repair brecing for concrete slabs, beams, columns, lintels chijk etc curved or straight including fitting fixing, and striking out after completion of works. (a) 25mm to 37.5mm. Thick wooden shuttering as per decision & direction of Engineer-In-Charge.	434m2	m <sup>2</sup>	159.50	69223.00
6	Ordinary Cement concrete (3:1.5:1) with graded stone chips (20mm. Size) excluding				



NO.	Description of Items	Quantity	Unit	Rate	Amount
	shuttering and reinforcement.	80 m <sup>3</sup>	m <sup>3</sup>	4546.80	363744.00
7.	Filling in foundation or plinth By silver sand	97.20	M3	270.50	26292.60
8.	Reinforcement for reinforced Ccrete Worki in all Sorts of structure				
	Including distribution bars, stirrups ,binders etc including supply				
	Of roads, initial straightening and removal of loose rust				
	(if necessary), cutting to requisite length, hooking and bending				
	To correct shape ,placing in proper position and bending				
	Tor steel/ mild steel	8.47	MT	40000.00	338800.00
9.	1 <sup>st</sup> class Brick Wark (250mm)Thick Cement mortar (6:1) In super structure. B) In superstructure.	20.05m3	m <sup>3</sup>	3047.80	61108.39
				Total Rs=	930057.00
			Add @ 1%	Cess Rs	9300.57
			Add @3%	Contingency	27901.71
				Total Rs =	967259.28
				Say Rs =	967259.00

  
**Sub- Assistant Engineer**  
**Joynagar Mozilpur Municipality**  
**South 24 Parganas**

  
**CHAIRMAN**  
**Joynagar Mozilpur Municipality**  
**South 24 Parganas**

Proposed Estimated for Construction of  
 Hospital Building (M.E.W.E) at Joynagar  
 Mojilpur Municipality, South-24 parganas

- ① Earth work in Excavation of foundation Trenches.  
 Depth of Excavation not Exceeding - 1500mm.  $18 \times 2.5m \times 2.5m \times 1.2m = 135m^3$
- ② Earth work in filling with Excavated Earth.  $27m^3$
- ③ Single layer B.P.S of picked Thama bricks in all Floor.  $18(2.5m \times 2.5m) = 112.5m^2$   
 say  $113m^2$
- ④ Filling in foundation of plinth by Silver Sand.  $18m \times 9m \times .6m = 97.2m^3$
- ⑤ Cement Concrete with graded Thama Khoa (30mm size) excluding shuttering and reinforcement in ground Floor & Foundation.  $18(2.5m \times 2.5m \times 0.15m) = 16.86m^3$
- ⑥ Hire & Labour charge for shuttering & Centering = For Slab  $= (19m \times 10m) = 190m^2$   
 For Column  $= 18 \{ 2(3 \times 3.75) + 2(3 \times 2.5) \} = 67.5m^2$   
 For ~~Rob~~ beam  $= 2 [ 3(19m \times 3) \times 2 + (19m \times 2.5m) ] = 96m^2$   
 For Tie beam  $= 5(10m \times 3m) + 5(10m \times 2.5m) = 27.5m^2$

For Footing =  $18 (2.5m \times 2.5m) \times 4 = 45m^2$

For Chajja =  $10m \times 6m = 6m^2$

Total  $432m^2$  say  $434m^2$

⑦ Nominal mix Concrete

(1:1.5:3) with graded stone chips (20mm size).

For Footing =  $18 \times 2.5m \times 2.5m \times 0.25m = 28.12m^3$

For pedestal =  $18m \times 375 \times 375 \times 45m$

For Slab =  $19m \times 10m \times 0.125m = 23.75m^3$

For Column =  $18 (2.5m \times 375m \times 2.7m) = 4.55m^3$

For Roof beam + tie beam =  $2 [5 (2.5m \times 3m \times 10) + 3 (2.5m \times 3m \times 19m)] = 16.04m^3$

For Stairs Case =  $(12.5m \times 1.8m \times 12.5m) + 20 \times \frac{1}{2} \times 1.5 \times 1.9m = 5.66m^3$

Total =  $79.25m^3$   
say  $80m^3$

⑧ Reinforcement for reinforced concrete work in all sorts of structure including distribution bars.

1.35% Total volume of concrete

$\frac{1.35 \times 80m^3 \times 7850}{100 \times 1000}$

= 8.47 MT

⑨ Bricks work with 1st class Bricks in Cement Sand mortar (6:1) in Super Structure.

$3 (19m \times 2.5m \times 7.5m) = 10.68m^3$

$5 (10m \times 2.5m \times 7.5m) = 9.37m^3$

20.05m<sup>3</sup>



**SUDA**

# STATE URBAN DEVELOPMENT AGENCY

HEALTH WING

"ILGUS BHAVAN"

H-C BLOCK, SECTOR-III, BIDHANNAGAR, CALCUTTA-700 091  
West Bengal

Ref No. ....SUDA-Health/527/09/483

Date .....01.12.2009

**From : Director, SUDA**

**To : Shri A.K. Das, IAS  
Project Director, HSDI,  
Commissioner, Family Welfare &  
Spl. Secretary  
Dept. of Health Family Welfare**

**Sub. : Submission of Utilisation Certificate.**

**Ref. : Communication of DHFW bearing no. HFW/HSDI/230/HHW-193/06  
dt. April 24, 2008.**

**Sir,**

Enclosed kindly find herewith Utilisation Certificate (UC) in respect of fund released towards construction of one portion of the Annexed Hospital Building of the Maternity & Child Welfare centre under Joynagar Mazilpur Municipality, South 24 Parganas.

Thanking you.

Yours faithfully,

**Encl. : (1) Communication of DHFW.  
(2) Utilisation Certificate.**

**Director, SUDA**

SUDA-Health/527/09/483/1(2)

**Dt. .. 01.12.2009**

CC

1. Dr. S.P. Banerjee, Jt. DHS & SFWO, DHFW.
2. Shri K.L. Bhowmick, OSD, HSDI, DHFW

**Director, SUDA**

**Utilisation Certificate**  
**(Form No. S.R. 330 A)**


Sl. No.	Ch. No. & Date	Amount (in Rs.)
1.	Ch. No. 020225 dt. 05.05.2008 United Bank of India, Salt Lake Branch, Sector - V vide GO No. HFW/HSDI/230/HHW-193/06 dt. 24 <sup>th</sup> April, 2008	8,13,592.00
	<b>Total</b>	

Certified that out of Rs. 8,13,592/- of Grants-in-aid sanctioned during the year 2008-09 in favour of Director, SUDA towards construction of one portion of the Annexed Hospital Building of the Maternity & Child Welfare centre under Joynagar Mazilpur Municipality, South 24

Parganas under this Ministry / Department letter no. given in the margin and a sum of Rs. 8,13,592/- has been utilized for the purpose it was sanctioned.

Certified that I have satisfied myself that the conditions on which the Grant-in-aid was sanctioned has been duly fulfilled / are being fulfilled and that I have exercised the following checks to see that the money was actually utilized for the purpose for which it was sanctioned.

**Signature of Director, SUDA**

  
04-12-09

**SUDA**

**STATE URBAN DEVELOPMENT AGENCY**

**HEALTH WING**

**"ILGUS BHAVAN"**

H-C BLOCK, SECTOR-III, BIDHANNAGAR, CALCUTTA-700 091  
West Bengal

Ref No. ....SUDA-Health/527/09/483

Date .....01.12.2009

**From : Director, SUDA**

**To : Shri A.K. Das, IAS  
Project Director, HSDI,  
Commissioner, Family Welfare &  
Spl. Secretary  
Dept. of Health Family Welfare**

**Sub. : Submission of Utilisation Certificate.**

**Ref. : Communication of DHFW bearing no. HFW/HSDI/230/HHW-193/06  
dt. April 24, 2008.**

Sir,

Enclosed kindly find herewith Utilisation Certificate (UC) in respect of fund released towards construction of one portion of the Annexed Hospital Building of the Maternity & Child Welfare centre under Joynagar Mazilpur Municipality, South 24 Parganas.

Thanking you.

Yours faithfully,

**Encl. : (1) Communication of DHFW.  
(2) Utilisation Certificate.**

*Sdt*

**Director, SUDA**

SUDA-Health/527/09/483/1(2)

**Dt. .. 01.12.2009**

CC

1. Dr. S.P. Banerjee, Jt. DHS & SFWO, DHFW.
2. Shri K.L. Bhowmick, OSD, HSDI, DHFW

**Director, SUDA**

**STATE URBAN DEVELOPMENT AGENCY****HEALTH WING****"ILGUS BHAVAN"****H-C BLOCK, SECTOR-III, BIDHANNAGAR, CALCUTTA-700 091  
West Bengal**Ref No. ....**SUDA-Health/527/09/483**Date .....**01.12.2009****From : Director, SUDA****To : Shri A.K. Das, IAS  
Project Director, HSDI,  
Commissioner, Family Welfare &  
Spl. Secretary  
Dept. of Health Family Welfare****Sub. : Submission of Utilisation Certificate.****Ref. : Communication of DHFW bearing no. HFW/HSDI/230/HHW-193/06  
dt. April 24, 2008.****Sir,**

Enclosed kindly find herewith Utilisation Certificate (UC) in respect of fund released towards construction of one portion of the Annexed Hospital Building of the Maternity & Child Welfare centre under Joynagar Mazilpur Municipality, South 24 Parganas.

Thanking you.

Yours faithfully,

**Enclo. : (1) Communication of DHFW.  
(2) Utilisation Certificate.****Director, SUDA****SUDA-Health/527/09/483/1(2)****Dt. .. 01.12.2009****CC**

- 1. Dr. S.P. Banerjee, Jt. DHS & SFWO, DHFW.**
- 2. Shri K.L. Bhowmick, OSD, HSDI, DHFW**

**Director, SUDA**

**FORM OF UTILISATION CERTIFICATE PRESCRIBED IN S. R. 330 OF THE  
TREASURY RULES, WEST BENGAL. AND THE SUBSIDIARY RULES  
MADE THEREUNDER, VOLUME-1.**

Certified that out of Rs. 8,13,592/- (Rupees Eight Lacs Thirteen Thousand five hundred & ninety-two only) of grant-in-aid sanctioned during the year 08-09 in favour of Joynagar Mozilpur Municipality under the Municipal services department Government order No. given in the margin Rs. N i L

on account of unspent balance of previous year & a sum of Rs. 8,13,592/- (Rupees Eight Lacs Thirteen Thousand five hundred & ninety-two only) has been utilised for the purpose for which it was sanctioned and that the balance of Rs. N i L

remaining un-utilised at the end of October, 20

Sl. No.	G.O. No & Date	Amount
1.	SUDA-Health/63 ULBs/- Accts /08/125 : 30.06.08	Rs. 8,13,592/-

Rupees Eight Lacs Thirteen Thousand five hundred & ninety-two only

(Through draft no. 043963  
dated - 28.06.08)

The YEAR has been carried over to be utilised in the subsequent year.

2. Certified that I have satisfied myself that the conditions on which the grants-in-aid was sanctioned have been duly fulfilled / are being fulfilled and that I have exercised the following checks to see that the money was actually utilised for the purpose for which was sanctioned.

Kinds of check exercised -


- 1.
- 2.
- 3.

The grants - in - aid were drawn under T. V. No. ....

Memo No. - JMN/Health/426

Dated - 05.11.09

To  
The Director  
SUDA  
"Health-Wing"  
9LGUS, BHAVAN  
Brahamnagar  
Kolkata - 700 091.



*[Signature]*  
Chairman 05/11/09

Joynagar Mozilpur Municipality.



Dr. Talukdar  
TO be kept  
in MH File  
4.9.09



FORM OF UTILISATION CERTIFICATE PRESCRIBED IN S. R. 330 OF THE  
TREASURY RULES, WEST BENGAL. AND THE SUBSIDIARY RULES  
MADE THEREUNDER, VOLUME - 1.

Certified that out of Rs. 8,13,592/- (Eight lakhs thirteen thousand -  
Five hundred ninety two only) of grant-in-aid sanctioned during  
the year 08-09 in favour of Joynagar Mozilpur Municipality under the Municipal services  
department Government order No. given in the margin Rs. Nil

.....  
on account of unspent balance of previous year & a sum of Rs. 7,32,300/- (Seven -  
Lakhs thirty two thousand three hundred only)  
has been utilised for the purpose for which it was sanctioned and that the balance of Rs. 81,292/-  
(Eighty one thousand two hundred ninety two only)  
..... remaining un-utilised at the end of 31/3/09

Sl. No.	G.O. No & Date	Amount
	SUDA/HEALTH/63/DLB/ACCTS/08/125 X, 30/6/08	

The YEAR has been carried over to be utilised in the subsequent year.

2. Certified that I have satisfied myself that the conditions on which the grants-in-aid was sanctioned have been duly fulfilled / are being fulfilled and that I have exercised the following checks to see that the money was actually utilised for the purpose for which was sanctioned.

Rs. 813592/-  
(Rupees eight lakhs thirteen thousand -  
Five hundred ninety two only)

Kinds of check exercised -

- 1.
- 2.
- 3.

The grants - in - aid were drawn under T. V. No. ....

Memo No. - J.M.M/Health/57

Dated - 15.05.09

To,  
The Director,  
SUDA. Health Wing  
ILGUS Bhavan, Sec-III  
Kolkata - 91



*[Signature]*  
Chairman

Joynagar Mozilpur Municipality.

**SUDA**

**STATE URBAN DEVELOPMENT AGENCY**

**HEALTH WING  
"ILGUS BHAVAN"**

H-C BLOCK, SECTOR-III, BIDHANNAGAR, CALCUTTA-700 091  
West Bengal

Ref No **SUDA-Health/63 ULBs/Accts./08/125**

Date .....**30.06.2008**

**From : Finance Officer, SUDA**

**To : The Chairman  
Joynagar Mazilpur Municipality**

**Sub. : Release of fund for construction of one portion of the annexed Hospital building of Maternity and Child Welfare Centre under Joynagar Mazilpur Municipality, South 24 Parganas.**

**Sir,**

With reference to your proposed estimate for construction of one portion of the annexed Hospital building of Maternity and Child Welfare Centre dt. 22.01.2008, I am to intimate you that Dept. of Health & Family Welfare has sanctioned Rs. 8,13,592/- (Rupees Eight lakhs thirteen thousand five hundred ninety two) only towards construction as mentioned above. For this purpose, an A/C payee demand draft bearing no. 043963 dt. 28.06.2008, on SBI, Salt Lake for the said amount is released to meet up the expenditure towards said construction. You are requested kindly to send your authorized representative along with money receipt to collect the said draft from the A/C section of SUDA.

You are requested to undertake such construction observing Procurement Rules of Government of West Bengal. It may be noted that the fund so released should be strictly used for the purpose mentioned above.

You are requested to complete the work by November, 2008 and forward a completion statement in this regard along with Utilisation Certificate to the undersigned immediately as soon as expenditure is incurred.

It is to be noted that this is **one time support** without creating any precedence.

Thanking you.

Yours faithfully,

**Finance Officer, SUDA**

Contd. to P-2.

- 2 -

**SUDA-Health/63 ULBs/Accts./08/125/1(2)**

**Dt. .. 30.06.2008**

**Copy forwarded for kind information to :**

- 1. Executive Officer, Joynagar Mazilpur Municipality**
- 2. Finance Officer, Joynagar Mazilpur Municipality**



**Finance Officer, SUDA**

**SUDA-Health/63 ULBs/Accts./08/125/2(1)**

**Dt. .. 30.06.2008**

**Copy forwarded for kind information to :**

**Project Officer, Health, SUDA**



**Finance Officer, SUDA**

**SUDA**

# STATE URBAN DEVELOPMENT AGENCY

HEALTH WING  
"ILGUS BHAVAN"

H-C BLOCK, SECTOR-III, BIDHANNAGAR, CALCUTTA-700 091  
West Bengal

Ref No **SUDA-Health/63 ULBs/Accts./08/125**

Date .....**30.06.2008**

**From : Finance Officer, SUDA**

**To : The Chairman  
Joynagar Mazilpur Municipality**

**Sub. : Release of fund for construction of one portion of the annexed Hospital building of Maternity and Child Welfare Centre under Joynagar Mazilpur Municipality, South 24 Parganas.**

Sir,

With reference to your proposed estimate for construction of one portion of the annexed Hospital building of Maternity and Child Welfare Centre dt. 22.01.2008, I am to intimate you that Dept. of Health & Family Welfare has sanctioned Rs. 8,13,592/- (Rupees Eight lakhs thirteen thousand five hundred ninety two) only towards construction as mentioned above. For this purpose, an A/C payee demand draft bearing no. 043963 dt. 28.06.2008, on SBI, Salt Lake for the said amount is released to meet up the expenditure towards said construction. You are requested kindly to send your authorized representative along with money receipt to collect the said draft from the A/C section of SUDA.

You are requested to undertake such construction observing Procurement Rules of Government of West Bengal. It may be noted that the fund so released should be strictly used for the purpose mentioned above.

You are requested to complete the work by November, 2008 and forward a completion statement in this regard along with Utilisation Certificate to the undersigned immediately as soon as expenditure is incurred.

It is to be noted that this is **one time support** without creating any precedence.

Thanking you.

Yours faithfully,

*Sdr*  
**Finance Officer, SUDA**

Contd. to P-2.

- 2 -

**SUDA-Health/63 ULBs/Accts./08/125/1(2)**

**Dt. .. 30.06.2008**

**Copy forwarded for kind information to :**

- 1. Executive Officer, Joynagar Mazilpur Municipality**
- 2. Finance Officer, Joynagar Mazilpur Municipality**

*Sdr*

**Finance Officer, SUDA**

**SUDA-Health/63 ULBs/Accts./08/125/2(1)**

**Dt. .. 30.06.2008**

**Copy forwarded for kind information to :**

**Project Officer, Health, SUDA**



**Finance Officer, SUDA**

## রাজ্য নগর উন্নয়ন সংস্থা

## STATE URBAN DEVELOPMENT AGENCY

“ইলগাস ভবন”, এইচ-সি ব্লক, সেক্টর-৩, বিধাননগর, কলকাতা ৭০০ ১০৬, পশ্চিমবঙ্গ  
 “ILGUS BHAVAN”, HC Block, Sector-III, Bidhannagar, Kolkata 700 106, West Bengal

SUDA-67/2006/ 4/3

23.06.2008

ক্রমিক নং .....

তারিখ .....

From : Director, SUDA

To : The Manager,  
 State Bank of India,  
Salt Lake City, Kolkata - 700 091.

**Sub : Preparation of Account Payee Demand Draft  
 Current Account No.10836424685.**

**Community Based Primary Health Care Services**

Sir,

You are requested to kindly arrange for preparation of the following Account Payee Demand Drafts as per details given below, debiting the amount from this office Current Account No.10836424685 lying with your branch in respect of Community Based Primary Health Care Services.

Sl. No.	Name of Payee	Amount (in Rs.)	SBI Branch
1.	Chairman, Jainagar-Mazilpur Municipality	813592.00	Baruipur
<b>Total</b>		<b>813592.00</b>	
<b>(Rupees Eight Lakh Thirteen Thousand Five Hundred Ninety-two only)</b>			

  
 (Debasis Mitra)  
 Joint Secretary  
 M.A.Department, GOWB

  
 (C. Sircar)  
 Director  
 SUDA

Sub. : Release of fund for construction of one portion of the annexed Hospital building of the Maternity and Child Welfare Centre under Joynagar Mazilpur Municipality, South 24 Parganas.

Enclosed the copy of communication of Project Director, HSDI, Commissioner, Family Welfare & Special Secretary, DHFW bearing no. HFW/HSDI/230/HHW-193/06 dt. 24<sup>th</sup> April, 2008 addressed to the undersigned.

DHFW has released a sum of Rs. 8,13,592/- (Rupees Eight lakhs thirteen thousand five hundred ninety two) only for meeting the non-recurring expenditure towards construction of annexed portion of Hospital building under Joynagar Mazilpur Municipality.

It is learnt from DHFW that the cheque for the above mentioned amount has been drawn in favour of "Director, SUDA" bearing no. 020225 dt. 05.05.2008, UBI, Salt Lake Branch. Necessary action may kindly be taken to collect the said cheque from DHFW by your authorized representative.

Submitted.

Director, SUDA

S. S. S. S. S.  
27-5-08

GOVERNMENT OF WEST BENGAL  
DEPARTMENT OF HEALTH & FAMILY WELFARE  
HEALTH SYSTEM DEVELOPMENT INITIATIVE  
SWASTHYA BHAWAN, GN-29, SECTOR-V  
SALT LAKE CITY, KOLKATA - 700 091  
TEL: 2357 4455

April 24, 2008

No.HFW/HSDI/230/HHW-193/06

**From: A. K. Das, IAS**  
Project Director, HSDI,  
Commissioner, Family Welfare & Special Secretary

**To: Dr. Shibani Goswami,**  
Project Officer, Health, SUDA,  
Ilgus Bhavan  
Block-HC, Sector-III,  
Bidhan Nagar,  
Salt Lake, Kolkata - 700091.



**Sub:** Release of fund for construction of one portion of the Annexed Hospital Building of the Maternity and Child Welfare Centre under Joynagar Mazilpur Municipality, South 24 Parganas.

Madam,

In inviting reference to your letter no. SUDA/Health/63/ULBs/07/764 dated 19.03.2008 this is to inform you that a sum of Rs. 8,13,592 (Rupees eight lakh thirteen thousand five hundred ninety two) only is hereby released in your favour for meeting the non-recurring expenditure towards construction of one portion of the Annexed Hospital Building of Maternity & Child Welfare Centre under Joynagar Mazilpur Municipality, South 24 Parganas as per plan and estimate prepared by the Sub-Assistant Engineer, Joynagar Mazilpur Municipality and approved by the Executive Engineer, HSDI on behalf of this Department.

The Joint Director (Accounts), HSDI will act as the Drawing and Disbursing Officer for the purpose.

The charge is debitable to the head of Account under "Grants-in-Aid" provision of HSDI Fund from the budgetary allocation for the year 2008-09.

It may be noted that the fund so released should be strictly used for the purpose mentioned above. Copy of the plan and estimate in respect of the work are being returned herewith for execution.

The Utilisation Certificate duly supported by the Statement of Expenditure in respect of the fund should be submitted to the undersigned immediately as soon as the expenditure is incurred and latest by 31<sup>st</sup> December, 2008.



This order is issued under the authority of power delegated to the Additional Chief Secretary of Health and Family Welfare Department, Government of West Bengal under Finance Department's Memo No. 10637-F dated 23.12.2005.

You are requested to kindly send your authorized representative to collect the cheque from the Accountant, HSDI at Swasthya Bhavan, Salt Lake, Kolkata.

Yours faithfully,

Sd/-  
(A. K. Das)


Project Director, HSDI, Commissioner, F.W..  
& Special Secretary

No.HFW/HSDI/230/HHW-193/06

April 24, 2008

Copy forwarded for information and necessary action to the:

1. Principal Secretary, Municipal Affairs Department, Writers' Buildings, Kolkata - 700001.
2. Joint Secretary, Municipal Affairs Department, Writers' Buildings, Kolkata - 700001.
3. Director, SUDA, Ilgus Bhavan, HC Block, Sector-III, Bidhannagar, Kolkata - 700091.
4. Executive Director, West Bengal State Health and Family Welfare Samiti.
5. Joint Director (Accounts), HSDI.
6. Advisor, HMIS.
7. OSD, HSDI.
8. OSD, RCH-II (MA).
9. Guard File.
10. Office Copy.



(A. K. Das)

Project Director, HSDI, Commissioner, F.W..  
& Special Secretary