

NABADIGANTA INDUSTRIAL TOWNSHIP AUTHORITY

UNNYAN BHAVAN, 1ST FLOOR, BLOCK-A, SEC-II, SALT LAKE CITY, KOLKATA-700091

NIQ NO. 11/NDITA/2014-2015

Dated: 09.12.2014

NOTICE INVITING QUOTATION

Sealed Quotation are invited by the **Executive Officer, Nabadiganta Industrial Township Authority** for the under mentioned work from bonafide, eligible and experienced Firms/Individual Contractors who have successfully completed works in Govt. Deptt.'s/ Local Bodies having credentials i.e. work orders with Completion Certificates of executing at least 50% value of similar nature of work in a single contract, within the stipulated time.

Name of the work:	As per enclosed list.
Value of the work	To be quoted in enclosed separate sheet.
Last date and time for submission of sealed Quotation	Up to 3.00 p.m. on 17.12.2014
Date and time for opening of Quotation in presence of willing Quotationers	After 3.30 p.m. on 17.12.2014

2. Qualification of Quotationers:

The intending quotationer should possess requisite well established infrastructure to carry out similar type of work including possessions of qualified supervisors, skilled and unskilled work force and sufficient resourcefulness, equipment, required for proper execution of work, being applied for.

3. Credentials, certificates, testimonials etc required along with application for Quotation documents:

- i) Experience certificates of similar type of completed works if any in various Govt./ Statutory Body/ Local body / Govt. undertaking Authorities. The minimum limit of total value of work, for which certificates to be attached, should be not less than 50% of corresponding value of work, each year for last three years. The certificates should invariably include work orders supported by payment certificates, performance certificate issued by relevant authorities from where orders / payment certificates have been originated.

- ii) Valid Sales, Commercial Tax, Professional Tax certificates, Income Tax Return verification form of last Assessment Year along with Quotation.
- iii) Trade License issued by competent authority.
- iv) Certificate of registration of West Bengal Value Added Tax in Form 3.

4. Earnest Money payable along with submitted Quotation:

- i) An amount of Rs. 3,000/- (Rupees three thousand only) shall have to be paid by Quotationer in form of Bank Draft of any Nationalized Bank drawn in favor of NDITA.

5. Quotation Documents: The Quotation shall consist of –

- i) Trade License issued by competent authority.
- ii) Certificate of registration of West Bengal Value Added Tax in Form 3.
- iii) Pro-forma of Bid Quotation.
- iv) Notice Inviting Quotation.

6. Conditional Quotation:

No conditional Quotation shall be entertained.

7. Right to acceptance:

The Quotation inviting authority reserves the right to accept the Quotation. He also reserves the right to reject one, few or all Quotation received. The decision of the authority is final, without assigning any reason whatsoever and shall be binding for all.

8. Validity for acceptance:

Offers made in Quotation shall remain valid up to 90 (Ninety) days from the date of submission of Quotation. No revision on any ground shall be entertained at any stage.

9. General:

Mode and method for quoting rates and other input, spirit and features of the contract and all relevant aspects have been highlighted in the different section of the Quotation document, which shall be governing and binding condition of the contract.

10. Related information about the work site etc.:

The Quotationers are advised to ascertain the site conditions fully prior to submission of Quotation. They may also seek prior clarifications on various related aspects of the work. No claims on ground of insufficient knowledge on any count after submission of the Quotation shall be entertained.

11. Late submission of the Quotation documents is not allowed.

12. **No subletting** of works by initiating any type of **sub-contract**, is allowed.

13. Conditional Quotation will not be accepted in any case.

14. All intending eligible applicant(s)is/are requested to be present personally during the time of submitting application. Authorized representative through Notary/Power of Attorney will only be allowed in absence of original applicant(s)

Executive Officer
Nabadiganta industrial Township Authority

Memo No: 1486/1(10)/NDITA/14

Date: 09.12.2014

Copy forwarded for kind information and with request for publicity to:-

1. The Chief Engineer, Municipal Engineering Directorate, Bikash Bhavan, Bidhannagar, Kolkata- 700091.
2. Secretary KMDA, Prasasan Bhavan, Bidhannagar.
3. Sub- Divisional Officer, Bidhannagar
4. Executive Officer, Bidhannagar Municipality
5. Technical Advisor/NDITA
6. The Executive Engineer/ NDITA.
7. The Finance Officer/ NDITA
8. The Notice Board, NDITA.
9. Publication in our official website (www.ndita.org) & website of the Deptt. of M.A. (www.wbdma.gov.in)
10. Publication in daily news papers

Executive Officer
Nabadiganta industrial Township Authority

NABADIGANTA INDUSTRIAL TOWNSHIP AUTHORITY

Unnayan Bhavan, 1st Floor, Block - A, Sector - II, Salt Lake, Kolkata - 700 091

LIST OF WORKS UNDER NIQ NO: 11/NDITA/2014-15 OF E.O.

Dated: 09.12.2014

Sl. No.	Name of work	Time of Completion
1.	Construction of bamboo fencing on the footpath (Left side) from T.C.S. to Plasto Chemicals under NDITA.	21 Days
2.	Construction of bamboo fencing on the footpath from Technopolis to Box bridge in NDITA.	21 Days
3.	Construction of bamboo fencing in the service road median from Nicco park to Nabajyoti Sporting Club (near Chingrighata more) under NDITA.	21 Days
4.	Construction of bamboo fencing in the median from (i) College more to Ring road, (ii) Chingrighata to Nabajyoti Sporting Club near Chingrighata more under NDITA.	21 Days
5.	Supply & Plantation of Trees and plants in the green verge along the eastern side of eastern drainage channel, medians from Bowlers' Den to SDF more, SDF more to Nayapatti more including one month maintenance.	30 Days
6.	Operation & maintenance of the following water fountain for a period of 12 (twelve) months. I. Foam Jet fountain inside the median at AL-BL junction. II. Foam Jet fountain inside raised garden near IIPM building. III. Cascade fountain in the green verge by the side of E.D. Channel near proposed metro station. IV. Foam Jet fountain in the raised garden in front of Technopolis.	Period of work:- 12 Months
7.	On call trimming of trees at Nabadiganta Industrial Township Area for 1 (one) year.	Period of work:- 12 Months

Executive Officer
Nabadiganta industrial Township Authority

Rate Sheet for work in NIQ No. 11/NDITA/2014-15 Sl. 1

Name of work : Construction of bamboo fencing on the footpath (Left side) from T.C.S. to Plasto Chemicals under NDITA.

<u>Sl. No.</u>	<u>Description of work</u>	<u>Qty.</u>	<u>Unit</u>	<u>Rate to be quoted (Rs.)</u>
1.	Construction of bamboo fencing made with 75mm dia bamboo post at an interval of 1.60mtr. with length of bamboo post 1.60mtr. embedding 0.600mtr. below G.I. necessary digging holes in all sorts of Soil upto a depth of 600mm and filling the digging earth for fixing the post as per direction. Bamboo runner made with 1/4 th split bamboo of 75mm dia bamboo placed horizontally (4Nos. horizontal runner) and nailing with necessary size of nails and vertical railing of spacing 200mm with quarter bamboo of 75mm dia including cost of nailing complete with 2(Two) coats of synthetic enamel paint over a coat of wooden primer as per direction E.I.C.	480.00 Mtr.	Per Mtr.	
		Total -		Rs.

Amount in word:-

Signature of Quotationer
(with Seal)

Rate Sheet for work in NIQ No. 11/NDITA/2014-15 Sl. 2

Name of work : Construction of bamboo fencing on the footpath from Technopolis to Box bridge in NDITA.

<u>Sl. No.</u>	<u>Description of work</u>	<u>Qty.</u>	<u>Unit</u>	<u>Rate to be quoted (Rs.)</u>
1.	Construction of bamboo fencing made with 75mm dia bamboo post at an interval of 1.50mtr. with length of bamboo post 1.25mtr. embedding 0.600mtr. below G.L. necessary digging holes in all sorts of Soil upto a depth of 600mm and filling the digging earth for fixing the post as per direction. Bamboo runner made with 1/2 nd split bamboo of 75mm dia bamboo placed horizontally (3Nos. horizontal runner) and nailing with necessary size of nails and vertical railing of spacing 175mm with quarter bamboo of 75mm dia including cost of nailing complete with 2(Two) coats of synthetic enamel paint over a coat of wooden primer as per direction of E.I.C.	895.00 Mtr.	Per Mtr.	

Total -

Rs.

Amount in word:-

Signature of Quotationer
(with Seal)

Rate Sheet for work in NIQ No. 11/NDITA/2014-15 Sl. 3

Name of work : Construction of bamboo fencing in the service road median from Nicco park to Nabajyoti Sporting Club (near Chingrighata more) under NDITA.

<u>Sl. No.</u>	<u>Description of work</u>	<u>Qty.</u>	<u>Unit</u>	<u>Rate to be quoted (Rs.)</u>
1.	Construction of bamboo fencing made with 75mm dia bamboo post at an interval of 1.60mtr. with length of bamboo post 1.60mtr. embedding 0.600mtr. below G.I. necessary digging holes in all sorts of Soil upto a depth of 600mm and filling the digging earth for fixing the post as per direction. Bamboo runner made with 1/4 th split bamboo of 75mm dia bamboo placed horizontally (4Nos. horizontal runner) and nailing with necessary size of nails and vertical railing of spacing 200mm with quarter bamboo of 75mm dia including cost of nailing complete with 2(Two) coats of synthetic enamel paint area coat of wooden primer as per direction E.I.C.	1400.00 Mtr.	Per Mtr.	
Total -				Rs.

Amount in word:-

Signature of Quotationer
(with Seal)

Rate Sheet for work in NIQ No. 11/NDITA/2014-15 Sl. 4

Name of work : Construction of bamboo fencing in the median from (i) College more to Ring road, (ii) Chingrighata to Nabajyoti Sporting Club near Chingrighata more under NDITA.

<u>Sl. No.</u>	<u>Description of work</u>	<u>Qty.</u>	<u>Unit</u>	<u>Rate to be quoted (Rs.)</u>
1.	Construction of bamboo fencing made with 75mm dia bamboo post at an internal of 1.60mtr. with length of bamboo post 1.60mtr. embedding 0.600mtr. below G.I. necessary digging holes in all sorts of Soil upto a depth of 600mm and filling the digging earth for fixing the post as per direction. Bamboo runner made with 1/4 th split bamboo of 75mm dia bamboo placed horizontally (4Nos. horizontal runner) and nailing with necessary size of nails and vertical railing of spacing 200mm with quarter bamboo of 75mm dia including cost of nailing complete with 2(Two) coats of synthetic enamel paint area coat of wooden primer as per direction E.I.C.	1080.00 Mtr.	Per Mtr.	
		Total -		Rs.

Amount in word:-

Signature of Quotationer
(with Seal)

Rate Sheet for work in NIQ No. 11/NDITA/2014-15 Sl. 5

Supply & plantation of trees & plants in the green verge along the eastern side of Eastern Drainage Channel, medians from Bowlers Den to SDF more to Nayapatty More including one month maintenance.

Sl. No.	Description	Qty.	Unit	Rate to be quoted
1.	Supply of Plumeria (Red & White) 5 ft.-6 ft.. height, ready trees, bushy type in large polybag base including carriage, loading and unloading at site and plantation by cutting hole 2ft.x2ft.x2ft and filling of existing good earth with mixing of necessary fertilizer and one month maintenance.	20 Nos.	Each	
2.	Supply of Arica Palm 6ft.-7ft. height, ready trees, bushy type in large polybag base including carriage, loading and unloading at site and plantation by cutting hole 2ft.x2ft.x2ft. and filling of existing good earth with mixing of necessary fertilizer and one month maintenance.	75 Nos.	Each	
3.	Supply of Ficus (Yellow) 3 ft. - 4 ft. height, ready trees, bushy type in larged polybag base including carriage, loading and unloading at site and plantation by cutting hole 2 ft.x2ft.x2ft. and filling of existing good earth with mixing of necessary fertilizer and one month maintenance.	400 Nos.	Each	
4.	Supply of Buddha's Belly Bamboo 5ft. - 6ft. height, ready trees, bushy type in large polybag base including carriage, loading and unloading at site and plantation by cutting hole 2ft. x2ft.x2ft. and filling of existing good earth with mixing of necessary fertilizer and one month maintenance.	100 Nos.	Each	
5.	Supply of Rhaps Palm 5ft.-6ft height, ready trees, bushy type in larged polybag base including carriage, loading and unloading at site and plantation by cutting hole 2ftx2ftx2ft and filling of existing good earth with mixing of necessary fertilizer and one month maintenance.	100 Nos.	Each	
6.	Supply of Ficus Panda 1 ft - 6 inch. to 2ft. height, ready trees, bushy type in larged polybag base including carriage, loading and unloading at site and plantation by cutting hole 2ft x 2ft x 2ft. and filling of existing good earth with mixing of necessary fertilizer and one month maintenance.	200 Nos.	Each	

7.	Supply of Ficus Yellow 1 ft. - 6 inch. to 2ft. height, ready trees, bushy type in larged polybag base including carriage, loading and unloading at site and plantation by cutting hole 2ft x2ft x2ft and filling of existing good earth with mixing of necessary fertilizer and one month maintenance.	100 Nos.	Each	
8.	Supply of Ficus Nudablack 1 ft – 6 Inch to 2 ft. height, ready trees, bushy type in large polybag base including carriage, loading and unloading at site and plantation by cutting hole 2ft. x2 ft.x2 ft. and filling of existing good earth with mixing of necessary fertilizer and one month maintenance.	200 Nos.	Each	
9.	Supply & Plantation of Lantana Plants 1 ft. height (Yellow colour, flower) with mixing necessary fertilizers and maintenance for 1 (one) month.	5000 Nos.	Each	
10.	Supply & Plantation of Acalypha Plants 1 ft. height with mixing necessary fertilizers and maintenance for 1 (one) month.	1000 Nos.	Each	
11.	Supply & Plantation of Tacoma Plants 1 ft.-1 ft 6 inch. height with mixing necessary fertilizers and maintenance for 1 (one) month.	50 Nos.	Each	
12.	Supply & Plantation of Alamunda Plants 1 ft. - 6 Inch - 2 ft.. height with mixing necessary fertilizers and maintenance for 1 (one) month.	300 Nos.	Each	
13.	Supply & Plantation of Ixora Chinensis Plants 1 ft. - 1 ft - 6 inch. with mixing necessary fertilizers and maintenance for 1 (one) month.	300 Nos.	Each	
14.	Supply & Plantation of Bougainvillea Bettina Plants 1 ft. - 6 Inch. to 2 ft with mixing necessary fertilizers and maintenance for 1 (one) month.	500 Nos.	Each	
Total -				Rs.

Amount in word:-

Signature of Quotationer
(with Seal)

Rate Sheet for work in NIO No. 11/NDITA/2014-15 Sl. 6
(Consolidated rate to be quoted for the work of four nos. fountain)

Name of Work: **Operation & maintenance of the following water fountain for a period of 12 (twelve) months.**

- I. Foam Jet fountain inside the median at AL-BL junction.**
- II. Foam Jet fountain inside raised garden near IIPM building.**
- III. Cascade fountain in the green verge by the side of E.D. Channel near proposed metro station.**
- IV. Foam Jet fountain in the raised garden in front of Technopolis.**

<u>Sl. No.</u>	<u>Description of work</u>	<u>Qty.</u>	<u>Rate to be quoted (Rs.)</u>
1.	Periodical maintenance of fountain including servicing, clearing, changing of bulb and holder, replacement of coloured paper or LED bulbs, rectification of electrical panel, replacement of nozzles, repair of pump etc.	4 Nos. fountain	

Total - Rs.

Amount in word:-

Signature of Quotationer
(with Seal)

Rate Sheet for work in NIQ No. 11/NDITA/2014-15 Sl. 7

**Name of work: On call trimming of trees at Nabadiganta Industrial Township Area for 1
(one) year.**

<u>Sl. No.</u>	<u>Description of work</u>	<u>Qty.</u>	<u>Unit</u>	<u>Rate to be quoted (Rs.)</u>
1.	Trimming of trees by engaging adequate labour for the work and disposal of cutted branches etc. within the day or day after the day, beyond the area of Nabadiganta Industrial Township including costs of all tools & tackles and transportation charges, cess, taxes etc. i) Trees at beyond 5mtr. from G.L. ii) Trees/Shrubs from G.L. to 5Mtr.	2000 Nos. 800 Nos.	Per No. Per No.	
Total -				Rs.

Amount in word:-

Signature of Quotationer
(with Seal)