

Memo No. CMU - 26/2002(Pt.-III)/711

Dated..27.02.13

NOTICE INVITING TENDER

Sealed tenders are invited from reliable and resourceful Contractors experienced in similar type of work for the following work.

Name of Work:- Renovation of office space on the 2nd floor of CDMC Building in ILGUS Campus to accommodate State RAY Technical Cell.

Estimated Cost :- Rs.5,12,400/-.

Intending bidders may inspect the proposed location on any working day between 2.00 P.M. to 4.00 P.M. from 27/02/2013 to 05/03/2013 (both days included).

The Contractor should quote their rates for individual items of work on percentage basis (above / below / at par) of the rates shown in the price schedule enclosed herewith (**Annexure : 1**).

Tenders completed in all respects along with credentials should reach the office of the **Project Director, CMU, ILGUS Bhavan, HC-Block, Sector-III, Bidhannagar, Kolkata – 700 106** on or before 21/03/2013 within 3.00 P.M. (Indian Standard Time).

Tenders will be opened on the same day (21/03/2013) at 4.00 P.M. in the presence of the participating bidders or their representatives.

The quoted rate shall be inclusive of all taxes, duties, delivery, fitting, fixing etc. complete.

The tender documents may be downloaded from www.changekolkata.org and www.wbdma.gov.in

The undersigned reserves the right of rejecting any or all the tenders without assigning any reason.

(M.N. Pradhan)
Project Director, CMU

Annexure : 1

ESTIMATE FOR THE WORK OF RENOVATION OF NEW OFFICE SPACE AT 3RD FLOOR

Sl. No.	Description	Quantity	Unit	Rate	Amount
1	Wood work in door and window frame with rebate cutting, fitted and fixed in position complete including a protective coat of painting at the contact surface of the frame excluding cost of concrete, Iron Butt Hinges and M.S clamps. P- 107, I -1(g)	0.65	Cum	59532.00	
2	Supplying, fitting and fixing boiling water resistant 19mm ply conforming to IS: 303-1989 bonded with phenol formaldehyde synthetic resin of approved make and brand fitted and fixed as per design as per approval and direction of Engineer-in-Charge.[excluding the cost of supporting frame work and teak wood batten/Lipping] In Ground Floor P-160, I-108(vi)	102	Sqm	1800.15	
3	Supplying fitting, fixing decorative lamination conforming to IS: 2046 : 1995 as per approved make, brand, finish and thickness with fitting, fixing the same on Particle/MDF / Ply Boards with recommended / approved adhesive with proper clipping the sides for better attachment as per direction of Engineer-in-charge. The rate includes the cost of labour, adhesive and all incidental charges thereof. In ground floor Glossy/Matt/Suede excluding surface texture or metallic lustre. P-166, I-121(i) (i) Thickness of laminate 1.5mm	48	Sqm	848.02	
4	Renewing wood moulding (50mm x 37.5m) of panel partition or panel door. (c) With Gamari wood. P-207, I-51(c)	285	Mtr	133.54	
5	Supplying best Indian laminated safety glass 8 mm. thick including cutting to required sizes, setting on putty bases and fitted and fixed with teak glazing beads (19 mm x 12mm) including putty and nails as necessary complete.(In all floors for internal wall & upto 6 m height for external wall). P-219, I-6	5	Sqm	2296.84	
6	French polishing to wood work including preparing surface (ordinary gloss) (a) On new wood work. P-217, I-18(a)	70	Sqm	370.11	

Annexure : 1

ESTIMATE FOR THE WORK OF RENOVATION OF NEW OFFICE SPACE AT 3RD FLOOR

Sl. No.	Description	Quantity	Unit	Rate	Amount
7	Supplying solid flush type doors of commercial quality, the timber frame consisting of top and bottom rails and side styles of well seasoned timber 65mm wide each and the entire frame fitted with 37.5mm wide battens places both ways in order to make the door of solid core and internal lipping with Garjan or similar wood veneers using phenol formaldehyde as glue etc. complete, including fitting, fixing shutters in position but excluding the cost of hinges and other fittings in ground floor. (a) 35 mm thick shutters (single leaf) P-157, I-101(a)	1.95	Sqm	2447.64	
8	Partition with soft insulation board (of 12mm thick) as per design fitted and fixed complete (excluding the supporting framework but including necessary teak wood battens of size 40 mm & 25 mm). In Ground Floor (a) Ordinary Teak. P-164, I-119(a)	2.5	Sqm	578.59	
9	ii) Hydraulic door closer fitted and fixed complete as per ISI standard. (a) Heavy type. P-121, I-43(ii)(a) (I.S.I. size 3)	1	Each	916.21	
10	Anodised aluminium butt hinges of approved quality manufactured from extruded section conforming to I.S specification (I.S: 205/66) and fitted and fixed with cadmium plated screws: (x) 150 x 75 x 4.0mm. P-126, I-64(x)	3	Each	139.90	
11	Supplying 'Godrej' mortice lock chromium plated with keys 6 levers including fitting & fixing complete. P-120, I-36(b)	1	Each	1407.04	
12	Brass floor door stopper. P-120, I-39(i)	1	Each	123.08	
13	Renewing M.S. clamps for door and window frame made of flat bent bar, end bifurcated with necessary screws etc. In cement concrete(1:2:4) including cutting of brick work/concrete work as per direction. (Cost of concrete will be paid separately). P-114, I-19(b) (b) 40mm X 6mm, 200mm Length	8	Each	41.15	

Annexure : 1

ESTIMATE FOR THE WORK OF RENOVATION OF NEW OFFICE SPACE AT 3RD FLOOR

Sl. No.	Description	Quantity	Unit	Rate	Amount
14	Anodised aluminium D-type handle of approved quality manufactured from extruded section conforming to I.S specification (I.S: 230/72) fitted and fixed complete: (a) With continuous plate base (Hexagonal / Round rod) (vii) 150 mm grip x 12 mm dia rod. P-127, I-65(a)(vii)	46	Each	118.96	
15	Anodised aluminium butt hinges of approved quality manufactured from extruded section conforming to I.S specification (I.S: 205/66) and fitted and fixed with cadmium plated screws: (iv) 75 x 63 x 3.2mm. P-126, I-64(iv)	20	Each	58.02	
16	Supplying, hi-back revolving chair for staff.(Godrej)	9	Each	10000.00	
17	Three seater sofa set with cushion & side arm with one no. centre table (3'-0" x 1'-3")	1	Each	27500.00	
18	Soft board velvet cloth.	6	Mtr	600.00	
19	Hydraulic channel	45	Each set	378.00	
20	Multi purpose lock (Godrej)	55	Each	170.00	
21	Wiring with 1.1 KV grade single core PVC insulated standard copper wire in EI Conduit / GI conduit and painting. B) 2X2.5 sqmm wire in 19mm conduit incl. S&F 1X14 swg GI ECC p-e-8 i-1b(Elct.Sch.)	15	RM	240.00	
22	Suppling & fixing 250 volt 3 pin 15 amp flush type plug socate with 15 amp switch piano type (Anchor Make) on sheet metal box with Bacholite top cover qand earthing attachment incl. S&F sheet metal box of size 175 X 100 mm (16swg) with 3 mm thick bacholite top cover. p-d-5, i-4 (Elect. Sch.)	10	Each	352.35	

Annexure : 1

ESTIMATE FOR THE WORK OF RENOVATION OF NEW OFFICE SPACE AT 3RD FLOOR

Sl. No.	Description	Quantity	Unit	Rate	Amount
23	Distribution wiring in 1.1 KV grade 2 X 22/0.3 (1.5 sqmm) single core standard "FR" PVC insulated & un sheathed copper wire (approved make) in suitable size pvc casting capping with 1 X 22/0.3 (1.5 sqmm) single core standard "FR" PVC insulated & un sheathed copper wire for ECC, incl. necy PVC CLIP fittings etc. to 5 AMP 3 pin flush type plug socate with piano type switch fixed to ms feb. switch board with bacolite top cover 3 mm thick flushed the wall by housing the board after cutting brick wall inclusive necessary connection making earthing attachment, painting and making goods damages to building works. p-e-20, i-6 (Elect. Sch.)				
	a) on Board	10	Each	75.00	
	b) Average run 3 mtr.	5	Each	505.00	